

CSST Tubing with vent through outside wall under slab installations.
No less than Schedule 40 PVC or ABS- DWV
Must be 10' away or 3' above air vent or air intake.

